8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for constructing Line Inspectors' Quarters at Kankanhalli.

	Items of work	Per	Main building quantity	Out-houses quantity
1.	Earthwork excavation and filling in basement	C. yd.	46	16
2.	Concrete in chunam	C. ft.	286	...
3.	Stone in mortar foundation and basement	"	1,152	579
4.	Burnt brick in clay, superstructure	"	1,988	548
5.	Do mortar do	"	490	271
6.	Burnt stone slabs, dressed and fixed	S. ft.	499	132
7.	Teakwood panelled door with iron clamps hinges lock, etc. ..	"	56	...
8.	Do windows with glazed shutters, iron bars, etc. ..	"	48	...
9.	Do batten doors, with iron clamps, etc.	"	130	116
10.	Do windows do bars, etc.	"	48	60
11.	Do panelled shelves with cross planks, varnishing, etc. ...	"	48	...
12.	Teakwood work, wrought and putt up, with wood oiling ...	C. ft.	69·25	27·0
13.	Roofing with 1st class Mangalore tiles, teak reepers, etc.	Sq.	15·75	6·20
14.	Ridge tiles set in mortar and cement painted	R. ft.	38	38
15.	Chunam plastering	Sq.	40·00	17·60
16.	White and colorwashing	"	40·00	17·60
17.	Teakwood eave boarding, ordinary	R. ft.	159	107
18	Do pendants	No.	4	4
19.	Do finials	"	2	2
20.	Flooring with Mangalore tiles over 3" chunam concrete and cement pointing.	Sq.	3·60	..
21.	Flooring with Cudappah slabs flooring chunam concrete and cement pointing.	"	4·50	2·40
22.	Chunam borders over gable reeds	R. ft.	76	26
23.	Painting doors and windows	Sq.	8·50	4·77
24.	Chunam pointing to basement	"	1·66	1·60
25.	Burnt brick in mortar coping with mortar plastering ...	R. ft.	..	32
26.	Gravel flooring compound	C. yd.	...	19
27.	Constructing chimneys	No.		2

S. G. FORBES,
Chief Electrical Engineer
to the Government of Mysore.

WATER-SUPPLY DIVISION.

Abstract Notification.

The attention of the public is invited to Notice, dated the 29th August 1918, calling for tenders for the suply of 4" and 5" C. I. pipes required for use of the Water-Supply Division, until the 23rd September 1918, published on page 782, Part II of the *Mysore Gazette*.

Abstract Notification.

The attention of the public is invited to the Notification appearing in the *Mysore Gazette* dated the 29th August 1918, calling for tenders for the supply of plain zinc sheets up to 16th September 1918, published in page 801 of the *Mysore Gazette* dated 5th September 1918.

NOTICE.

Tenders for the supply of the articles noted below will be received by the undersigned up to the 23rd September 1918.

2. Each tender should be accompanied by a deposit of Rs. 500 in Government Currency notes as earnest money and should be sent in a sealed cover superscribed "Tenders for the supply of 16" C. I. Y. pipes, etc.

3. The final acceptance of the tender will rest with the Superintending Engineer, Southern Circle, who does not bind himself to accept the lowest or any tender or assign any reason whatever for the rejection of any tender.

4. Within eight days if the accepted tender, successful competitor will be required to execute the usual contract bond, in default of which his tender will be cancelled and his earnest money forfeited.

5. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the undersigned's office in the usual course and no enquiries regarding the acceptance or rejection of a tender will receive any reply.

6. On acceptance of one of the tenders, the earnest money on rejected tenders will be refunded.

7. The quotation should be for delivery of the specials F. O. R. Coromandal Railway Station, Kolar Gold Fields Railway.

List of articles required.

(1) of 16" C. I. Y. Pipe as per Ferro Print, which can be had on application.
(4) of C. I. Spring Bends do do
(1) C. I. Sluice Valve with spigot and socket tail pieces.
(5) of 16" × 6" C. I. Branches.
(2) of 6" C. I. Sluice Valves with spigot snd socket tail pieces.

The thickness of metal to be as per standard trade practice and should have a coating of Dr. Augus Smith's solution.

S. SRINIVASA AIYAR,
Executive Engineer.